# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/RD/WORK_INDENT14126

## APPROVED SCHEDULE - B

**No. E/BTP/BBMP/E-PMT/07/2014-15, Date: 31.10.2014**

**Improvements to Roads and Drains at BEL 2nd Block 5th Cross Road Right Side in Ward No. 10 (Doddabommasandra), Vidyaranyapura Sub Division.**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of G VENKATE GOWDA | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 327.42 | Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work | Cum | 99.49 | Rupees Ninety Nine and Forty Nine Paise Only |
| 2 | 53.49 | mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete | Cum | 4556.22 | Rupees Four Thousand Five Hundred Fifty Six and Twenty Two Paise Only |
| 3 | 12.96 | masonry in superstructure with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work | Cum | 4487.18 | Rupees Four Thousand Four Hundred Eighty Seven and Eighteen Paise Only |
| 4 | 21.6 | Providing ruled pointing to coursed stone masonry with cement mortar 1:4, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications cement mortar 1:4. etc complete as per specifications and directions of engineer in charge of the work | Sqm | 87.31 | Rupees Eighty Seven and Thirty One Paise Only |
| 5 | 5.76 | mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per | Cum | 5007.98 | Rupees Five Thousand Seven and Ninety Eight Paise Only |
| 6 | 818.38 | Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work | Sqm | 275.12 | Rupees Two Hundred Seventy Five and Twelve Paise Only |
| 7 | 110.49 | of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation | Cum | 5701.36 | Rupees Five Thousand Seven Hundred One and Thirty Six Paise Only |
| 8 | 82.87 | straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery etc complete as per | Qtl | 7497.25 | Rupees Seven Thousand Four Hundred Ninety Seven and Twenty Five Paise Only |

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

| | | | | | |
|---|---|---|---|---|---|
| 9 | 278.31 | Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading etc complete as per specifications and directions of engineer in charge of the work | Cum | 64.76 | Rupees Sixty Four and Seventy Six Paise Only |

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92